PARKHOUSE ENTERPRISES LTD.

INDEPENDENT CONSULTANTS & SPECIALIST MATERIAL SUPPLIERS

3 Dunstan Hill, Kirton in Lindsey, Gainsborough, North Lincolnshire DN21 4DU

Telephone (01652) 648270 : E-mail ParkhouseEnt@aol.com

CEMENT TEST RESULTS

Client	:-	**Dragon Cement 42.5N**		
Our Reference	:-	**DG42-1**		
Your Reference	:-			
Sample	:-	**CEM 1 42.5N**		
Sample Date	:-			
Sand	:-	**German**		
Date of receipt of sample	:-	**21-Dec-13**		
Date of tests	:-	**23-Dec-13**	**to**	**20-Jan-14**

RESULTS

INITIAL SETTING TIME	**214 mins**	(BS EN196 PART 3:2005)

COMPRESSIVE STRENGTH :- MORTAR PRISMS (BS EN196 PART 1:2005)

AT 2 DAYS	**28.8 MPa**	(Mean of 6 results,none discarded)
AT 28 DAYS	**58.1 MPa**	(Mean of 6 results,none discarded)

CHEMICAL COMPOSITION :- by mass

Loss on ignition	**2.21 %**	(BS EN196 PART2:2013)
Insoluble Residue	**0.39 %**	(BS EN196 PART2:2013)

Signed..... **Date** **30-Jan-14**

S.Burton A.M.I.C.T **Technical Manager**

J.Burton **Quality Manger**