PARKHOUSE ENTERPRISES LTD.

INDEPENDENT CONSULTANTS & SPECIALIST MATERIAL SUPPLIERS

3 Dunstan Hill, Kirton in Lindsey, Gainsborough, North Lincolnshire DN21 4DU

Telephone (01652) 648270 : E-mail ParkhouseEnt@aol.com

CEMENT TEST RESULTS

Client	**:-**	**Dragon Cement 42.5R**		
Our Reference	**:-**	**DG42-5**		
Sample	**:-**	**CEM 1 42.5R**		
Sand	**:-**	**German**		
Date of receipt of sample	**:-**	**3-Feb-14**		
Date of tests	**:-**	**3-Feb-14**	**to**	**3-Mar-14**

RESULTS

INITIAL SETTING TIME	**165 mins**	(BS EN196 PART 3:2005)

COMPRESSIVE STRENGTH :- MORTAR PRISMS (BS EN196 PART 1:2005)

AT 2 DAYS	**31.0 MPa**	(Mean of 6 results,none discarded)
AT 28 DAYS	**58.1 MPa**	(Mean of 6 results,none discarded)

CHEMICAL COMPOSITION :- by mass

Loss on ignition	**2.52 %**	(BS EN196 PART2:2013)
Insoluble Residue	**0.44 %**	(BS EN196 PART2:2013)

Signed..... **Date 3-Mar-14**

S. Sykes Senior Technician