PARKHOUSE ENTERPRISES LTD.

INDEPENDENT CONSULTANTS & SPECIALIST MATERIAL SUPPLIERS

3 Dunstan Hill, Kirton in Lindsey, Gainsborough, North Lincolnshire DN21 4DU

Telephone (01652) 648270 : E-mail ParkhouseEnt@aol.com

CEMENT TEST RESULTS

Client	:-	Dragon Cement 52.5 R		
Our Reference	:-	DG52-4		
Sample	:-	CEM 1 52.5 R		
Sand	:-	German		
Date of receipt of sample	:-	27-Jan-14		
Date of tests	:-	27-Jan-14	to	24-Feb-14

RESULTS

INITIAL SETTING TIME	130 mins	(BS EN196 PART 3:2005)

COMPRESSIVE STRENGTH :- MORTAR PRISMS (BS EN196 PART 1:2005)

AT 2 DAYS	37.2 MPa	(Mean of 6 results,none discarded)
AT 28 DAYS	64.3 MPa	(Mean of 6 results,none discarded)

CHEMICAL COMPOSITION :- by mass

Loss on ignition	1.34 %	(BS EN196 PART2:2013)
Insoluble Residue	0.55 %	(BS EN196 PART2:2013)

Signed.....

S. Sykes Senior Technician

Date 24-Feb-14