PARKHOUSE ENTERPRISES LTD.

INDEPENDENT CONSULTANTS & SPECIALIST MATERIAL SUPPLIERS

3 Dunstan Hill, Kirton in Lindsey, Gainsborough, North Lincolnshire DN21 4DU

Telephone (01652) 648270 : E-mail ParkhouseEnt@aol.com

CEMENT TEST RESULTS

Client	**:-**	**Dragon Cement 52.5 R**		
Our Reference	**:-**	**DG52-5**		
Sample	**:-**	**CEM 1 52.5 R**		
Sand	**:-**	**German**		
Date of receipt of sample	**:-**	**3-Feb-14**		
Date of tests	**:-**	**3-Feb-14**	**to**	**3-Mar-14**

RESULTS

INITIAL SETTING TIME	**170 mins**	(BS EN196 PART 3:2005)

COMPRESSIVE STRENGTH :- MORTAR PRISMS (BS EN196 PART 1:2005)

AT 2 DAYS	**33.8 MPa**	(Mean of 6 results,none discarded)
AT 28 DAYS	**63.9 MPa**	(Mean of 6 results,none discarded)

CHEMICAL COMPOSITION :- by mass

Loss on ignition	**0.99 %**	(BS EN196 PART2:2013)
Insoluble Residue	**0.56 %**	(BS EN196 PART2:2013)

Signed..... **Date 3-Mar-14**

S. Sykes Senior Technician