PARKHOUSE ENTERPRISES LTD.

INDEPENDENT CONSULTANTS & SPECIALIST MATERIAL SUPPLIERS

3 Dunstan Hill, Kirton in Lindsey, Gainsborough, North Lincolnshire DN21 4DU

Telephone (01652) 648270 : E-mail ParkhouseEnt@aol.com

CEMENT TEST RESULTS

Client	:-	**Dragon Cement 52.5 R**
Our Reference	:-	**DG52-6**
Sample	:-	**CEM 1 52.5 R**
Sand	:-	**German**
Date of receipt of sample	:-	**10-Feb-14**
Date of tests	:-	**10-Feb-14 to 10-Mar-14**

RESULTS

INITIAL SETTING TIME	**160 mins**	(BS EN196 PART 3:2005)

COMPRESSIVE STRENGTH :- MORTAR PRISMS (BS EN196 PART 1:2005)

AT 2 DAYS	**34.6 MPa**	(Mean of 6 results,none discarded)
AT 28 DAYS	**63.7 MPa**	(Mean of 6 results,none discarded)

CHEMICAL COMPOSITION :- by mass

Loss on ignition	**1.25 %**	(BS EN196 PART2:2013)
Insoluble Residue	**0.41 %**	(BS EN196 PART2:2013)

Signed.....

S. Sykes Senior Technician

Date 11-Mar-14