PARKHOUSE ENTERPRISES LTD.

INDEPENDENT CONSULTANTS & SPECIALIST MATERIAL SUPPLIERS

3 Dunstan Hill, Kirton in Lindsey, Gainsborough, North Lincolnshire DN21 4DU

Telephone (01652) 648270 : E-mail ParkhouseEnt@aol.com

CEMENT TEST RESULTS

Client	:-	**Dragon Cement 42.5R**		
Our Reference	:-	**DG42-7**		
Sample	:-	**CEM 1 42.5R**		
Sand	:-	**German**		
Date of receipt of sample	:-	**18-Feb-14**		
Date of tests	:-	**18-Feb-14**	to	**18-Mar-14**

RESULTS

INITIAL SETTING TIME	**200 mins**	(BS EN196 PART 3:2005)

COMPRESSIVE STRENGTH :- MORTAR PRISMS (BS EN196 PART 1:2005)

AT 2 DAYS	**31.5 MPa**	(Mean of 6 results,none discarded)
AT 28 DAYS	**52.5 MPa**	(Mean of 6 results,none discarded)

CHEMICAL COMPOSITION :- by mass

Loss on ignition	**2.45 %**	(BS EN196 PART2:2013)
Insoluble Residue	**0.45 %**	(BS EN196 PART2:2013)

Signed..... **Date 18-Mar-14**

S. Sykes Senior Technician