

# **PARKHOUSE ENTERPRISES LTD.**

**INDEPENDENT CONSULTANTS & SPECIALIST MATERIAL SUPPLIERS**

**3 Dunstan Hill, Kirton in Lindsey, Gainsborough, North Lincolnshire DN21 4DU**

**Telephone (01652) 648270 : E-mail ParkhouseEnt@aol.com**

## **CEMENT TEST RESULTS**

<b>Client</b>	<b>:-</b>	<b>Dragon Cement 42.5R</b>	
<b>Our Reference</b>	<b>:-</b>	<b>DG42- 110</b>	
<b>Sample</b>	<b>:-</b>	<b>CEM 1 42.5R</b>	
<b>Sand</b>	<b>:-</b>	<b>German</b>	
<b>Date of receipt of sample</b>	<b>:-</b>	<b>03-Jul-16</b>	
<b>Date of tests</b>	<b>:-</b>	<b>03-Jul-16</b>	<b>to 31-Jul-16</b>

### **RESULTS**

**INITIAL SETTING TIME** **180 mins** (BS EN196 PART 3:2005)

**COMPRESSIVE STRENGTH :- MORTAR PRISMS** (BS EN196 PART 1:2005)

**AT 2 DAYS** **33.6 MPa** (Mean of 6 results, none discarded)

**AT 28 DAYS** **57.1 MPa** (Mean of 6 results, none discarded)

**CHEMICAL COMPOSITION :- by mass**

**Loss on ignition** **2.63 %** (BS EN196 PART2:2013)

**Insoluble Residue** **0.61 %** (BS EN196 PART2:2013)

**Sulphate** **3.42 %** (BS EN196 PART2:2013)

Signed.....

**S. Sykes Senior Technician**

**Date 03-Aug-16**