# PARKHOUSE ENTERPRISE LTD

INDEPENDENT CONSULTANTS & SPECIALIST MATERIALS SUPPLIERS

3 DUNSTAN HILL, KIRTON LINDSEY, GAINSBOROUGH, LINCOLNSHIRE DN21 4FG
PHONE: 01652 656931/01652648270 EMAIL: PARKHOUSEENT@AOL.COM


# CEMENT TEST RESULTS

| | | | |
|---|---|---|---|
| **Client** | **:-** | **Dragon Cement 42.5R** | |
| **Our Reference** | **:-** | **DG42-** | **163** |
| **Sample** | **:-** | **CEM 1 42.5R** | |
| **Sand** | **:-** | **German** | |
| **Date of receipt of sample** | **:-** | **13-Sep-17** | |
| **Date of tests** | **:-** | **13-Sep-17** | **to 11-Oct-17** |

**RESULTS**

| | | |
|---|---|---|
| **INITIAL SETTING TIME** | **156 mins** | **(BS EN196 PART 3:2005)** |
| **COMPRESSIVE STRENGTH :- MORTAR PRISMS** | | **(BS EN196 PART 1:2005)** |
| **AT 2 DAYS** | **29.8 MPa** | **(Mean of 6 results,none discarded)** |
| **AT 28 DAYS** | **52.1 MPa** | **(Mean of 6 results,none discarded)** |
| **CHEMICAL COMPOSITION :- by mass** | | |
| **Loss on ignition** | **3.24 %** | **(BS EN196 PART2:2013)** |
| **Insoluble Residue** | **0.50 %** | **(BS EN196 PART2:2013)** |
| **Sulphate** | **3.46 %** | **(BS EN196 PART2:2013)** |

***S.Sykes***

**Signed.....** **Date 11-Oct-17**

**S. Sykes Senior Technician**