PARKHOUSE ENTERPRISES LTD.

INDEPENDENT CONSULTANTS & SPECIALIST MATERIAL SUPPLIERS

3 Dunstan Hill, Kirton in Lindsey, Gainsborough, North Lincolnshire DN21 4DU

Telephone (01652) 648270 : E-mail ParkhouseEnt@aol.com

CEMENT TEST RESULTS

Client	:-	**Dragon Cement 42.5R**		
Our Reference	:-	**DG42- 58**		
Sample	:-	**CEM 1 42.5R**		
Sand	:-	**German**		
Date of receipt of sample	:-	**20-Apr-15**		
Date of tests	:-	**20-Apr-15**	**to**	**18-May-15**

RESULTS

INITIAL SETTING TIME	**210 mins**	**(BS EN196 PART 3:2005)**

COMPRESSIVE STRENGTH :- MORTAR PRISMS **(BS EN196 PART 1:2005)**

AT 2 DAYS	**30.5 MPa**	**(Mean of 6 results,none discarded)**
AT 28 DAYS	**53.0 MPa**	**(Mean of 6 results,none discarded)**

CHEMICAL COMPOSITION :- by mass

Loss on ignition	**2.37 %**	**(BS EN196 PART2:2013)**
Insoluble Residue	**0.74 %**	**(BS EN196 PART2:2013)**
Sulphate	**3.36 %**	**(BS EN196 PART2:2013)**

Signed..... **Date** **18-May-15**

S. Sykes Senior Technician